

# Building The Daniel K. Inouye Solar (DKIST) Telescope (formerly ATST)



PI  
National Solar Observatory

Co-PIs  
High Altitude Observatory  
New Jersey Institute of Technology  
University of Hawai'i  
University of Chicago

Stephen L. Keil  
NSO Emeritus Scientist







# What is the DKIST Project?


- ~Ten year long construction project (2010-2019)
  - Design and build project
  - 4-meter class solar observatory
- Funded by the National Science Foundation (NSF):
  - \$340M total cost (\$297M + recovery of mitigation funds)
    - \$146M American Recovery and Reinvestment Act of 2009 (ARRA)
    - Remainder Major Research Equipment & Facilities Construction (MREFC)




# PHOTOSPHERIC MAGNETIC FIELDS - plus or minus 10 gauss



## Yearly Averaged Sunspot Numbers 1610-2000







Courtesy F. Woeger

430nm



30" from Limb

0.058"/pixel


2K x 2K

100 frames/ 5 sec  
burst

~27 sec cadence





# Solar Wind and Mass Ejections





# Living with a star


(the many impacts of space weather)





# DKIST Science Objectives

## Magnetic Fields and Structure on their Fundamental Scales – a systems approach to the solar atmosphere

- Structure and dynamics of the solar atmosphere
  - Heating of chromosphere and corona
  - Flares and coronal mass ejections – fundamental physics of space weather drivers
  - Dynamo processes
  - Surface dynamo
- Precise magnetic field measurements throughout the dynamic solar atmosphere
  - Photosphere, chromosphere, coronal




Dunn Solar Telescope






# Why ATST Magnetoconvection




Magnetic Field




Intensity

# Comparison with other Telescopes


## Areal Resolution



# Resolution Elements



# Why DKIST Coronal and Chromospheric Heating




IBIS (tunable filter)  
at the  
Dunn Solar Telescope

Courtesy of Kevin Reardon


# Comparison with other Telescopes

**Fixed B, Fixed Size**  
(assumes same sensitivity)



# What is the DKIST



- 4m aperture, off-axis Gregorian (reflective)
- Altitude-over-azimuth mount
- Rotating coudé instrument platform
- Integrated adaptive optics
- Integrated Instrumentation
- Hybrid enclosure with thermal control and dust mitigation







# Telescope Mount Assembly (TMA)

- 4m aperture, off-axis Gregorian (reflective)
- Al-Az mount
- Rotating coudé instrument platform









# Testing Coudé Rotator








# M1 Assembly

2010				2011				2012				2013				2014				2015				2016				2017				2018				2019			
Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4				
Bid				Design				Procure, Fab, Test				Ship		SAT		IT&C																							

1. M1 Blank(s): Schott AG, Mainz, Germany
2. Figuring & Polishing: University of Arizona, College of Optical Sciences, Tucson, AZ
3. M1 Cell + Actuators + Thermal Control: AMOS SA, Angleur-Liege, Belgium



4m Primary Mirror Assembly



# M1 Assembly (cont.)



11/12/2014

Eclipse Workshop

21






# M2/Top End Optical Assembly

2010				2011			
Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4

Bid

- 
- 
- 
- 
- 



2018				2019			
Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4





Render courtesy L3-Brahear




# M2/Top End Optical Assembly - Testing

620 mm diameter  
Silicon-Carbide



# What is the DKIST

- Integrated adaptive optics.
- Fixed & visitor instrumentation
- Field of view: 5 arc minutes.
- Angular resolution 0.03 arc second (at 500nm).
- Polarization accuracy <0.01%
- Wavelength sensitivity from 0.3-28 microns.
- Service & PI access modes of operation









# DKIST Instruments

2010				2011				2012				2013				2014				2015				2016				2017				2018				2019			
Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
												Design				Procure, Fab, Test				Ship				Site Assembly & Test															

Cryogenic Near-Infrared Spectro-Polarimeter (Univ. of Hawai`i/IfA)




Diffraction-Limited Near-Infrared Spectro-Polarimeter (Univ. of Hawai`i/IfA)



Visible Spectro-Polarimeter (11/12/2014 Altitude Observatory)

Eclipse Workshop






Fabry-Perot Visible Tunable Filter (Kiepenheuer Institute for Solar Physics)



# DKIST Instruments (cont.)


## Visible Broadband Imager (NSO/DKIST Project)



# First Light Instrumentation

Adaptive Mirror and  
Wavefront Correction

Visible Tunable Filter  
Red Channel (VBI-R)  
Blue Channel (VBI-B)  
390 – 860 nm




Diffraction Limited Near-IR  
Spectro-Polarimeter (DL – NIRSP)  
900 – 2300 nm

at  
er (VISP)  
m  
-IR  
eter  
)  
m

# Enclosure

2010				2011				2012				2013				2014				2015				2016				2017				2018				2019						
Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4							
Bid	Design							Procure, Fab, Test							Ship	Site Assembly & Test																										

- Contract with AEC-IDOM, Minneapolis, MN and Bilbao, Spain:
  1. Design & Analysis
  2. Procure, Fabricate, Factory Assembly, Test, Disassemble, Pack & Ship
  3. (Site Erect)





# Enclosure Base Ring



# Arch Girders and Trusses

2013-06-24 17:33:51



11/12/2014



Eclipse Workshop

31



# Enclosure (cont.)



Shutter Drive "Crawler" Test Rig



Factory Assembly in Bilbao, Spain  
(July, 2013)



# ction



*Assembly of the*





*hutter Sector is  
ure*

# Site & Support Facilities Construction

2010				2011				2012				2013				2014				2015				2016				2017				2018				2019			
Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4
Design												Fab & Site Construction																											

- Architectural & Engineering (A&E): M3 Engineering, Tucson, AZ
- Construction: DKIST acting as General Contractor:
  - Excavation
  - Concrete
  - Steel Fab
  - Steel Erect/Assemble
  - Electrical
  - Mechanical
  - Finishwork/TI
  - 3<sup>rd</sup> Party Inspectors



# Where is DKIST being Built



11/12/2014


Image © 2009 DigitalGlobe  
Eclipse Workshop

©2009 Google 35

Eye alt 1236 ft



# Simplified Permitting Flow-Chart



# Ground Breaking Blessing Ceremony





# Ground Breaking Blessing Ceremony





# Early Site Construction



ATST Construction Webcam 2013-01-24 12:34:35




11/12/2014

# Site Construction Foundation Preparation










# DKIST atop Haleakalā, Maui

Artist Concept of  
Completed  
Telescope



# Contact Information

Stephen L. Keil  
[skeil@nso.edu](mailto:skeil@nso.edu)

Thomas Rimmele, Project Director, 1-575-434-7022

Joe McMullin, Project Manager, 1-520-318-8105

Tom Berger, Project Scientist, 1-575-7134

For More Information see:

<http://DKIST.nso.edu>



END